BOQ Civil Work DAVIM Faridabad

| S.No. | Description of Item | Quantity | Unit | Rate | Amount |
|-------|--|----------|------|------|------------|
| | Dismantling tile work in floors laid in cement mortar including disposal | | | | Filliodine |
| 1 | dismantled material outside the College primises. (Passage floor BBA Block) | 25 | Sqm | | |
| | Providing and laying rectified Glazed Ceramic floor tiles of size 300x300 mm | | | | |
| | of 1stquality conforming to IS: 15622, of approved make, laid on 20 mm | | | | |
| 2 | thick cement mortar 1:4(1 Cement: 4 Coarse sand), jointing with grey | | | | |
| | cement slurry @ 3.3kg/ sqm including grouting the joints with white cement | | | | |
| | and matchingpigments etc., complete (Passage floor BBA Block) | 25 | Sqm | | |
| | Amount | 1 | | | |
| | GST 18% extra if any | | | | |
| | Total Amount | | | | |