

**Name of Work: Painting Work at DAV Institute of Management at NIT-3,
Faridabad Haryana.**

You are invited to submit your competitive sealed, signed and stamped quotations for above noted Work at DAV Institute of Management at NIT-3, Faridabad Haryana. The general terms and conditions to execute the work are as mentioned below.

Terms and Conditions: -

1. Work shall be carried out as per CPWD specification of Volume-I and II with up-to-date correction slip.
2. Mode of Measurement as per Actual Measurement.
3. All Labour at site should wear safety equipment and follow all safety measures as required agency will be fully responsible for the safety of labourer. In case of any accident at site/injury caused to labour at site, contractor **will be fully responsible**
4. Deduction of taxes if any shall be as per norms.
5. Contractor raised RA bill Minimum amount Rs 2.50 Lakh.
6. The Security deposit will be collected by deductions from the running bills of the contractor @5% of the value of work done. No interest shall be paid on security deposit. Refund of security after 6 month completion of work.
7. The contractor should have valid GST registration number **and also mention** on each bill before submission.
8. It may also be noted that Client reserves the right to accept or reject any or all the quotations without assigning any reason thereof.
9. Bidder shall fill up the rate as per specification mentioned **In the BOQ.** (Material & Labour)
10. Contractors are advised to visit the site before offering **their rates if required.**
11. No Mobilization advance and No secured advance.
12. All Paints Asian make.
13. Providing Ladder, Jhullas, scaffoldings includes in rates, cleaning windows, Floors after Painting work includes in rates.
14. Work completion time will be 45 days. (Working hours 8 A.M. to 6 P.M.) From the date of work order or handover of site, whichever is earlier.
15. BOQ attached.

Dr Ritu Gandhi Arora
Officiating Principal



BOQ Painting Work DAVIM Faridabad

S.No.	Description of Item	Quantity	Unit	Rate	Amount
1	Distemping with oil bound washable distemper of approved brand and manufacture to give an even shade . In class Room , Passage. (Asian, Burger Make)				
a	Old work (Two coats)including repair work with white cement putty,cleaning surface with sandpaper.	30860	Sqft		
2	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.(Dismantling wall tile Area)	1320	Sqft		
3	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: (Plastered with Putty surface In Class Room wall) (Asian, Burger Make)		Sqft		
a	Two or more coats on new work over an under coat of suitable shade with ordinary paint of approved brand and manufacture	1320	Sqft		
4	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade: (Asian, Burger Make)		Sqft		
a	Old work (Two coats) (Class Room wall)	1310	Sqft		
5	Finishing walls with Acrylic Smooth exterior paint (Apex)of required shade :(Asian Make)		Sqft		
a	Old work (Two coats) including repair of Birla white cement wall putty work,cleaning surface with sandpaper.	8000	Sqft		
	Amount				
	GST 18% extra if any				
	Total Amount				

