BOQ Painting Work DAVIM Faridabad

	BOQ Painting Work DA		Unit	Rate	Amount
S.No.	Description of Item	Quantity	Offic	Nate	7
5.1101	Distempering with oil bound washable distemper of				
1	approved brand and manufacture to give an even shade				
	. In class Room , Passage. (Asian, Burger Make)	•			
а	Old work (Two coats)including repair work with white		6(1)		
	cement putty.cleaning surface with sandpaper.	30860	Sqft		
2	Providing and applying white cement based putty of				
	average thickness 1 mm, of approved brand and				
	manufacturer, over the plastered wall surface to prepare				
	the surface even and smooth complete.(Dismantling				
	wall tile Area)	1320	Sqft		
3	Painting with synthetic enamel paint of approved brand				
	and manufacture of required colour to give an even				
	shade: (Plastered with Putty surface in Class Room wall)	1	أغده		
	(Asian Burger Make)		Sqft	2724	
a	Two or more coats on new work over an under coat of				\$
	suitable shade with ordinary paint of approved brand		6-4		F
	and manufacture	1320	Sqft		
4	Painting with synthetic enamel paint of approved brand				
	and manufacture of required colour to give an even	•	Sqft		
	shade: (Asian, Burger Make)	1210	Sqft	7	
а	Old work (Two coats) (Class Room wall)	1310	Sqit		
5	Finishing walls with Acrylic Smooth exterior paint (Saft	, "	
	Apex)of required shade :(Asian Make)		Sqft		
а	Old work (Two coats) including repair of Birla white		, ,		
	cement wall putty work, cleaning surface with	8000	Sqft		
	sandpaper.	8000	Sqit	1 11 1	
6	Painting on G.S. sheet on Roof Terrace with synthetic				
	enamel paint of approved brand and manufacture of				
	required colour to give an even shade :	27000	Sqft		
а.	Old work (Two coats)	27000	Sqit	· • • • • • • • • • • • • • • • • • • •	
	Amount		40 7 A G 190	1 T T F T	
	GST 18% extra if any				
	Total Amount				